
Addendum No. 1 Acequia de la Muralla Diversion Dam Rehabilitation Project

This addendum is issued to reflect the following changes to the contract documents dated June 30, 2018. This Addendum is effective December 12, 2018. It shall be the responsibility of all bidders to adhere to any changes or revisions to the Acequia de la Muralla Diversion Dam Project as identified in this Addendum No. 1. This documentation shall become a part of the Contract Documents.

1. Attached is the attendance sheet from the December 11, 2018 pre-bid meeting.
2. On sheet 5 of 7, Construction Details, within the Irrigation Heading Structure Detail (bottom left corner of sheet 5), the following notes which references “CMP” shall be changed to read as follows:
 - A. Proposed Steel Collar, inside diameter to accommodate proposed HDPE Sluiceway Pipe. Provide water tight seal.
 - B. Proposed Steel Collar, inside diameter to accommodate proposed HDPE Canal Pipe. Provide water tight seal.
3. On sheet 3 of 7, Demolition Plan, the proposed temporary access location is shown to be along a straight line extending down the slope from the existing gravel parking lot. An alternative access location is located approximately 20 feet to the west. The alternative access may be used instead of the access shown on the plans, but must be restored in accordance with the contract documents.
4. On sheet 3 of 7, Demolition Plan, a note in the plan view states: “Install orange safety fence around perimeter of project site and trees marked by engineer for preservation. Clear and grub all non-native vegetation.” The orange safety fence shall extend around the project site, excluding along the sides of the temporary construction access from Upper Canyon Road, down to the toe of the slope at floodplain elevation. In accordance with Construction Specification 9 – Traffic Control, Contractor shall implement an Engineer-approved traffic control plan to manage public detours for both roadway and trails at the Project site.

Bids are due at 5:00 pm on December 18, 2018 at the office of William J. Miller Engineers, Inc., 1511 Third St., Santa Fe, NM 87505. Bids will be opened and read aloud at 5:00 pm on December 18, 2018 at the office of William J. Miller Engineers, Inc.

Acequia de La Muralla

Diversion Dam Rehabilitation: Pre-Bid Site Meeting

Tuesday, December 12, 2018

William J. Miller Engineers: 1511 Third St. Santa Fe, NM

Name	Organization	Phone #
William Rivera	TOTAL CONTRACTING SERVICES	505 800-7156
CJ MEAD	CJ MEAD CONST CO	WRIVERA@TCSI.US - VRAMIREZ@TCSI.US 505-269-3020
Johnny Manzon	New Image Const	TIMMS@ALDINE@HOTMAIL.COM NEW-IMAGE@MANZON & AUL.COM
Gabriel Serra	New Image	"
Clyde Alcar	Barney & Son	575-387-5800
JOHN CRITCHFIELD	WILLIAM J. MILLER ENGINEERS, INC.	505 983 7694
Jeremiah Kidd	San Isidro Permaculture	505-501-4769
ADRIENNE KOPLIK	THE PANCHATCHER	505-919-9014
Bruce A McWilliams	WJ Miller Engineers	505-983-7694
Patrick Herrera	Allied 360 Con	505 470-5779
Courtney Mathew	Acequia	980-9854
BC Rimbeaux	"	470-8090