
Addendum No. 1
Acequia Madre de Peñasco Sur
Diversion Dam Rehabilitation Project

This addendum, effective October 31, 2023, is issued to reflect the following changes to the contract documents dated October 25, 2023. This documentation shall become a part of the Contract Documents.

1. The sign-in sheet for the mandatory pre-bid meeting for **Monday October 30, 2023, is attached.**
2. Sheet 2 of the Contract Documents is to be replaced with the attached, containing a revised Bid Schedule with 2 new deductive alternatives. Bid item #14 shall contain the amount to be subtracted from the Base Bid for substitution of an epoxy paint coated steel irrigation heading structure in place of the reinforced concrete structure shown on sheet 6 of the Construction Drawings. After contract award, Contractor would submit for Engineer approval an epoxy paint submittal and shop drawing submittal for a ¼" thick steel structure to match the nominal inside dimensions of the concrete structure details. Bid item #15 shall contain the amount to be subtracted from the Base Bid for substitution of epoxy paint coated steel slide gates (42" x 42" and 36" x 36") in place of the aluminum slide gates specified in the Construction Drawings.
3. The landowner for the project site is **Estevan Lopez, (575) 770-0866**. The Contractor should anticipate that cattle will be present in and around the project site, including temporary access, temporary stockpile, and temporary staging areas. It is the responsibility of the Contractor to maintain a safe and secure environment for the cattle during construction. It is also the responsibility of the Contractor to coordinate with Mr. Lopez regarding any special conditions that may be required for granting access (ie: gate and/or culvert improvements). After the completion of the project, the disturbed portions of Mr. Lopez's land shall be neatly graded to a uniform slope and re-vegetated in accordance with General Note #9 on Sheet 1 of the Construction Drawings.

ACEQUIA MADRE DE PEÑASCO SUR DIVERSION
OAM REHABILITATION PROJECT

PRE-BID MEETING SIGN-IN

10/30/2023

10AM

<u>NAME</u>	<u>AFFILIATION</u>	<u>EMAIL</u>
John Critchfield	WJM Engineers, Inc.	john@wjmillereengineers.com
Tim Pacheco	Paul's building & Const	Pauls_bui_linc@hotmail.com
Chad Bygwell	Robins Construction	chad@robinsconstruction.com
Tim Spalding	C.I. Meese Const.	Timmspalding@hotmail.com
Vincent Abeyta	^{Acequia} President	S V Abeyta 51@gmail.com
Estevan Lopez	Land owner	estevan.lopez@outlook.com 575-770-0866

2. BID PROPOSAL

ACEQUIA PEÑASCO SUR DIVERSION DAM REHABILITATION

BID SCHEDULE						
BID ITEM NO.	SPEC. NO.	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	AMOUNT
1	8	Mobilization, demobilization	LS	1		
2	5	Pollution control	LS	1		
3	11	Control of water	LS	1		
4	7	Construction surveys	LS	1		
5	2	Clearing and demolition of existing dam, heading structure	LS	1		
6	21, 23	Earthwork (excavation and compacted backfill balanced on site)	CY	425		
7	61.A	Furnish and install structure rock (1.5 CY Boulders)	TN	298		
8	61.A	Furnish and install class C riprap	CY	173		
9	32	Furnish and install reinforced concrete	CY	8		
10	71	Furnish and install water control gates and miscellaneous metalwork	LS	1		
11	6	Planting, seeding, and stabilizing	SY	1010		
					SUBTOTAL:	
					NMGRT (6.875%):	
					GRAND TOTAL:	

DEDUCTIVE ALTERNATIVES				
12	61.A	Furnish and install class C riprap	EACH CUBIC YARD	
13	6	Plant Cottonwood Pole	EACH TREE	
14	71	Substitute installation of a epoxy paint coated steel irrigation heading structure in place of reinforced concrete structure	LUMP SUM	
15	71	Substitute installation of a epoxy paint coated steel slide gates in place of aluminum slide gates	LUMP SUM	

Contractor Name

Telephone Number

Street Address

NM State Contractor's License No.

City, State