

---

## Addendum No. 1 Acequia Madre de La Vegas Phase II Pipeline Project

---

This addendum is issued to reflect the following changes to the contract documents dated October 25, 2023. This Addendum is effective November 6, 2023. It shall be the responsibility of all bidders to adhere to any changes or revisions to the Acequia Madre de Las Vegas Phase II Pipeline Project as identified in this Addendum No. 1. This documentation shall become a part of the Contract Documents.

1. The sign-in sheet for the mandatory pre-bid meeting for Thursday November 2, 2023, is attached.
2. The due date and time for submittal of bids and the bid opening has been extended by one week. **Bids are due by 5:00 pm on November 16, 2023.**
3. There are **no changes** to the Contract Times listed in Article 3 of the October 25, 2023 Construction Documents.
4. The Bid Proposal (page 2-1) of the Construction Contract shall be replaced with Attachment 1 to this Addendum and shall include the following changes to the bid items:
  - A. Bid item No. 6, Clearing and Grubbing has been added to the base bid section.
  - B. Bid item No. 18, Deduct Clearing and Grubbing has been added to the alternatives section.
  - C. The remaining bid items have been renumbered.
5. Construction Specification 2 – Tree Clearing, included as Attachment 2 to this addendum, has been added to the construction specification.
6. Question: Are there any landowners that the Contractor may contact to arrange for a temporary equipment staging and material stockpile area?

Answer: The Contractor may contact the following landowners to negotiate a potential temporary equipment staging and material stockpile area(s):

NAME: Mike Cannone  
MAILING ADDRESS: 130 Alamo Street, Las Vegas, New Mexico, 877701  
PHONE: 505-652-9950  
PARCEL NUMBER: R0662443

NAME: Gary Ludie  
ADDRESS: 802 South Pacific, Las Vegas, NM 87701  
PHONE: 505-429-3009  
PARCEL NUMBER: R0008425

NAME: Kristine Ollickala  
ADDRESS: 231 Bernal Street, Las Vegas, NM 87701  
PHONE: 805-886-3176  
PARCEL NUMBER: R0654441

Acequia Madre de Las Vegas Phase II  
Pre-bid meeting 11/2/23 10:00 AM

Name	Company	email / Phone
Michael Lomato	SDI	sanchezdemolition@gmail.com
Steve Lucero	Acequia Madre	lucero steve 07 @ G.m.a.i
Dominic Lerma	Jim Sierra Const.	505-617-2601 575-472-3106 JSCCINC@Live.com
Bruce McWilliams	WJM Eng.	bruce@wjwillerengineers.com
Andy Stusser	WJM	505-983-7694 505-469-3111 andy@wsmillerengineering.com

Meeting completed @ 1200

## 2. BID PROPOSAL

### Acequia Madre de Las Vegas Pipeline Project – Phase II

BASE BID						
BID ITEM NO.	SPEC. NO.	DESCRIPTION	UNITS	QUANTITY	UNIT COST	TOTAL COST
1	8	Mobilization/demobilization	LS	1		
2	7	Construction Surveys	LS	1		
3	9	Traffic Control	LS	1		
4	9, 45, 39	City of Las Vegas Road Cut Permit	LS	1		
5	8	Demolition and removal of existing structures and rock ditch liner	LS	1		
6	2	Clearing and Grubbing	FT	1010		
7	45	Furnish and install 24" diameter PVC P.I.P.	LF	2565		
8	45	Furnish and install 24" diameter Schedule 40 steel pipe, and pipe supports	FT	60		
9	32, 45, 71	Furnish and install fittings valves, vents, end sections, cleanouts and trench boxes. See fitting schedule	LS	1		
10	32, 34, 71	Furnish and Install 4'x6' concrete trench box cleanout	LS	1		
11	45	Furnish and install pipeline bedding	CY	96		
12	45	Furnish and install (imported) compacted backfill	CY	1550		
13	21, 23	Earthwork (excavation and compacted backfill, balanced on-site)	CY	531		
14	39	Furnish and install 3" bituminous driveway	SY	23		
15	45	Furnish and install 6-12" riprap	CY	20		
					SUBTOTAL:	
					NMGRT(@8.1458%)	
					BASE BID TOTAL:	
BID ALTERNATIVES						
BID ITEM NO.	SPEC. NO.	DESCRIPTION	UNITS	UNIT COST		
16	21, 23 45	Deduct 24" diameter PVC P.I.P. 80 PSI (excavation, bedding and imported backfill)	FT			
17	32, 34, 45	Deduct Marmac coupler and reinforced concrete collar	EA			
18	2	Deduct Clearing and Grubbing	FT			

\_\_\_\_\_  
Contractor Name

\_\_\_\_\_  
Contractor Signature

\_\_\_\_\_  
Street Address

\_\_\_\_\_  
NM State Contractor's License No.

\_\_\_\_\_  
City, State

\_\_\_\_\_  
Telephone Number

## ***Construction Specification 2-- Clearing and Grubbing***

### **1. Scope**

The work consists of clearing and grubbing and disposal of trees, snags, logs, brush, stumps, shrubs, and rubbish from the ditch corridor.

### **2. Clearing and grubbing**

Trees, snags, logs, brush and stumps in the existing ditch corridor that obstruct the installation of the proposed pipeline or movement of equipment and materials may be cut and disposed of in a manner and at locations approved by the Engineer or Owner. Only trees, logs, snags, logs, brush and stumps within five feet of the centerline of the proposed pipeline alignment may be removed. The contractor is responsible for complying with all local rules and regulations and the payment of any and all fees that may result from disposal at locations away from the project site.

### **3. Measurement and payment**

Payment for clearing and grubbing is based on the linear foot of ditch corridor cleared. The sum of such payments shall constitute full compensation for clearing and grubbing (including the clearing and grubbing of smaller trees, stumps, snags, logs, brush, shrubs, and roots), applicable permits and associated fees, and rubbish removal. Such payment shall constitute full compensation for all labor, equipment, tools, and all other items necessary and incidental to the completion of the work.