Addendum No. 1 Acequia Madre de Las Vegas Phase 1 Pipeline Project

This addendum is issued to reflect the following changes to the contract documents dated October 27, 2021. This Addendum is effective November 12, 2021. It shall be the responsibility of all bidders to adhere to any changes or revisions to the Acequia Madre de Las Vegas Phase 1 Pipeline Project as identified in this Addendum No. 1. This documentation shall become a part of the Contract Documents.

- 1. The Bid Proposal (page 2-1) of the Construction Contract shall be replaced with Attachment 1 to this addendum and shall include the following changes to the bid items:
 - a. Bid item No. 13, Clearing and grubbing has been added to the base bid section.
 - b. Previous bid item 13 in the deductive alternatives is now bid item no. 14 and shall include tree clearing in the linear foot deductive alternative unit price.
 - c. The remaining bid items have been renumbered.
- 2. Construction Specification 2 Tree Clearing, included as Attachment 2 to this addendum, has been added to the construction specification.
- The due date and time for submittal of bids and the bid opening has been changed.
 Bids are due by 5:00 pm on November 23, 2021.

2. BID PROPOSAL (REVISED NOVEMBER 12, 2021)

ACEQUIA MADRE DE LAS VEGAS PIPELINE PROJECT PHASE I - STA 19+83 TO 31+08

		BID SCHEDULE			_	
BID ITEM	SPEC.					
NO.	NO.	DESCRIPTION BASE BID STA 19+83 TO STA 31+08 - IR	UNITS	QUANTITY DIDELINE	UNII COST	TOTAL COS
1	8	Mobilization/demobilization	LS	1		
2	7	Construction Surveys	LS	1		
3	5	Pollution Control	LS	1		
	9		LS			
<u>4</u> 5	3	Traffic Control Demolition and removal of existing structures	LS	1		
6	45	Furnish and install 24" diameter PVC P.I.P.	FT	1125		
7	32, 34, 45	Furnish and install fittings, valves, vents, cleanout and concrete inlet structure. See fitting schedule.	LS	1		
8	23, 45	Furnish and install pipeline sand bedding	CY	42		
9	23, 45	Furnish and install (imported) compacted backfill	CY	510		
10	21, 23	Earthwork (excavation and compacted backfill, balanced on-site)	CY	297		
11	45	Furnish and install 6-12" riprap	CY	20		
12	32, 34	Furnish and install Marmac coupler and reinforced concrete collar	LS	1		
13	2	Clearing and Grubbing	LF	1125		
				NMGRT	(@8.3958%): TOTAL:	
		DEDUCTIVE ALTERNA	TIVE			
NO.	SPEC. NO.	DESCRIPTION		UNITS UNIT P		UNIT PRICE
14	21, 23 45	Deduct 24" diameter PVC P.I.P. 80 PSI (including tree clearing, excavation, bedding and imported backfill)	LF	FOOT		
15	32, 34, 45	Deduct Marmac coupler and reinforced concrete collar	LS	EACH		
16	45	Deduct driveway @ STA 26+80 (includes 24 x 24 x12 T, riser, alfalfa valve, ARV with saddle, thrust block and CMP shelter w/ locking cap)	LS	EACH		
Contractor Name Street Address			Contractor Signature Telephone Number			
City, State, Zip			NM State Contractor's License No.			

2. Bid Proposal 2-1 October 27, 2021

Construction Specification 2-- Clearing and Grubbing

1. Scope

The work consists of clearing and grubbing and disposal of trees, snags, logs, brush, stumps, shrubs, and rubbish from the ditch corridor.

2. Clearing and grubbing

Trees, snags, logs, brush and stumps in the existing ditch corridor that obstruct the installation of the proposed pipeline or movement of equipment and materials may be cut and disposed of in a manner and at locations approved by the Engineer or Owner. Only trees,logs, snags, logs, brush and stumps within five feet of the centerline of the proposed pipeline alignment may be removed. The contractor is responsible for complying with all local rules and regulations and the payment of any and all fees that may result from disposal at locations away from the project site.

3. Measurement and payment

Payment for clearing and grubbing is based on the linear foot of ditch corridor cleared. The sum of such payments shall constitute full compensation for clearing and grubbing (including the clearing and grubbing of smaller trees, stumps, snags, logs, brush, shrubs, and roots), applicable permits and associated fees, and rubbish removal. Such payment shall constitute full compensation for all labor, equipment, tools, and all other items necessary and incidental to the completion of the work.